Excavation, depth 300mm 200m$^2$

| Window Schedule | |
|---|---|
| Family and Type | Count |
| | |
| Single-Light: 1212x1212 mm | 7 |
| Single-Light: 1212x2100 mm | 4 |

| Roof Schedule | |
|---|---|
| Family and Type | Area |
| | |
| Basic Roof: Warm - 400mm Roofing Tile / Timber | 113.48 m² |

| Door Schedule | |
|---|---|
| Family and Type | Count |
| | |
| Ext. Single-Flush in - Glass: 972x2145 | 1 |
| Int.Single-Flush: 912 x 2113 | 2 |

| Floor Schedule | |
|---|---|
| Family and Type | Area |
| | |
| Floor: Ground - 250mm Conc / Polystyrene - 100/150 | 70.13 m² |

| Wall Schedule | | |
|---|---|---|
| Family and Type | Area | Length |
| | | |
| Basic Wall: Ext - 408 mm Brick/ LW Conc - 108/180/120 | 25.17 m² | 10692 |
| Basic Wall: Ext - 408 mm Brick/Conc - 108/150/150 | 63.01 m² | 24876 |
| Basic Wall: Foundation - 390mm LW Thermo Block | 37.27 m² | 35496 |
| Basic Wall: Int - 100mm LW Concrete | 41.28 m² | 12888 |
| Chimney: Chimney | 0.39 m² | 0 |